

BID FORM
Phase 1 Shoreline Restoration
for
Blue Lake CDD

Revised February 19, 2026

Contractor:

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
I. Drainage Restoration					
2.0	Final Grading (Restore berm/rear swale to design grades per plans)	1	LS	\$0.00	\$0.00
3.0	Stabilize all impacted restored areas with sod (match existing species)	1	LS	\$0.00	\$0.00
Sub-Total Shoreline Restoration					\$0.00

23218 PARCEL	2-C	2-J	TOTAL	
PAVEMENT (SY)	11957.79	8758.51	20,716.30	
LIMEROCK (SY)	11957.79	8758.51	20,716.30	
STABILIZER (SY)	15111.87	11040.16	26,152.03	
SIDEWALK (SY)	2552.62	1892.8	4,445.42	
			-	
CURB			-	
2' VALLEY GUTTER (LF)	9569.88	6699.98	16,269.86	
TYPE "F" CURB (LF)	601.76		601.76	
TYPE "A" CURB (LF)		169.58	169.58	
			-	
ROADWAY SOD (SY)	2252	1521.44	3,773.44	25,882.76
LAKE SOD (SY)	3808.45	5655.42	9,463.87	
ADA (EA)	8	5	13.00	
			-	
WATER			-	
8" PVC DR-18 (LF)	4587.32	3351.74	7,939.06	8,312.80
8" PVC DR-14 (LF)	233.21	140.53	373.74	
8" GATE VALVE (EA)	15		15.00	
10" PVC DR-18 (LF)			-	
10" PVC DR-14 (LF)			-	
10" GATE VALVE (EA)			-	
FIRE HYDRANT (EA)	8	7	15.00	
			-	
IRRIGATION			-	
4" PVC DR-18 (LF)	4673.88	3170.68	7,844.56	
4" PVC DR-14 (LF)	228.91	144.03	372.94	
4" GATE VALVE (EA)	15	7	22.00	
8" PVC DR-18 (LF)			-	
8" PVC DR-14 (LF)			-	
8" GATE VALVE (EA)			-	
			-	
SANITARY			-	
8" SDR-26 (LF)	4722.73	3288.8	8,011.53	
4' MANHOLE (EA)	14	14	28.00	
6' MANHOLE (EA)	1		1.00	
LIFT STATION (EA)	1		1.00	
			-	
FORCEMAIN			-	
4" DR-18 (LF)	32.16		32.16	
4: DR-14 (LF)			-	
4" PLUG VALVE (EA)	1		1.00	
8" DR-18 (LF)			-	
8" DR-14 (LF)			-	
			-	
DRAINAGE			-	
YARD DRAIN (EA)	15	3	18.00	
30" ADS (LF)			-	
24" ADS (LF)	360.79		360.79	
18" ADS (LF)	84.4		84.40	
12" ADS (LF)	849.84	426.85	1,276.69	
48" RCP (LF)	385		385.00	
42" RCP (LF)	289.92		289.92	
36" RCP (LF)		1089.38	1,089.38	
30" RCP (LF)	1648.54	173.39	1,821.93	
24" RCP (LF)	213.5	202.39	415.89	
18" RCP (LF)	275.62	166.75	442.37	
JUNCTION BOX (EA)			-	
VGI (EA)	18	10	28.00	
TYPE "C" INLET (EA)	2	1	3.00	
TYPE "D" INLET (EA)			-	
TYPE "9" INLET (EA)			-	
48" HW (EA)	2		2.00	
36" HW (EA)		6	6.00	
30" HW (EA)	9	1	10.00	
24" HW (EA)	1	1	2.00	
			-	
CENTERLINE (LF)	4200.27	3388.3	7,588.57	
BERM SOD (SY)	11809.98	835.47	12,645.45	